



\* SEE MAG DET 505 FOR THESE DIMENSIONS

### NOTES:

1. UNLESS MODIFIED HEREON, THE CONCRETE COLLAR SHALL BE CONSTRUCTED AS SPECIFIED IN MAG DET 505
2. THE PIPE ENDS SHALL BE CUT TO MATCH THE PIPE DEFLECTION ANGLE
3. WIPE INSIDE OF COLLAR FLUSH AND SMOOTH WITH 3:1 SAND AND CEMENT MIX AND BRUSH SMOOTH
4. CONTRACTOR SHALL PROVIDE SANDBAGS, OR OTHER APPROVED METHOD, TO CONTROL PLACEMENT OF CONCRETE FOR COLLAR
5. ALL CONCRETE FOR THE COLLAR SHALL BE VIBRATED.

LAST UPDATED: 03/06/06

Roosevelt Water Conservation District

PIPE COLLAR (MAG 505 MODIFIED)